



Notes:

1. This is the City of Kalispell Design. A sample port is generally required as well (30" CB)
2. If INLET and outlet piping is greater than 4" than interior penetrations must match inlet and outlet
3. Use 1" Sealant
4. Drawing with Drive Over lid. City of Kalispell requires grade rings, and Sanitary sewer castings (non bolt down)
5. Reinforcement Drawings Available Upon Request.
6. Tank Designs Meet ASTM C1227, C890 & Montana DEQ Circular 4 With 6 Feet Of Bury.

Approx. Weight With Standard Lid = 10,370 Lbs.
 Approx. Weight With Traffic Rated Lid = 12,680 Lbs

	COMPANY: GLACIER PRECAST CONCRETE			CUSTOMER: Glacier Precast Concrete			MIX: MH4000	QUANTITY:
	TITLE: 1000 Gallon Sand Oil Sperator			PROJECT NAME:			CY:	SCALE: 1:20
	DRAWN BY: EP	DATE DRAWN: 3/25/2024	PM:	RELEASED FOR PROD.:	APPROX. DELIVERY:	WEIGHT:	SHEET: 1/1	

