



Note:

Two 8 ft strands of copper wire (#2) inside form. Copper wire attached to rebar using copper fargo clamp. and one 2 ft tail on the outside.

Utility anchors on the outside for picking

Open Bottom Available Upon Request

	COMPANY: GLACIER PRECAST CONCRETE			CUSTOMER: Glacier Precast Concrete				MIX: SCC 4000	QUANTITY:		
	TITLE: Three Phase Vault			PROJECT NAME:				CY: 1.81	SCALE: 1:30		
	DRAWN BY:EP	DATE DRAWN: 12MAR2025	PM:	RELEASED FOR PROD.:		APPROX. DELIVERY:		WEIGHT: 7,240 lbs	SHEET: 1/1		