



grounding wire inside not shown for clarity. See notes

Note:
Two 8 ft strands of copper wire (#2) inside form. Copper wire attached to rebar using copper fargo clamp. and one 2 ft tail on the outside.

Utility anchors on the outside for picking

Open Bottom Available Upon Request

	COMPANY: GLACIER PRECAST CONCRETE			CUSTOMER: Glacier Precast Concrete				MIX: SCC 4000	QUANTITY:		
	TITLE: Single Phase Vault			PROJECT NAME: FEC/Mission Valley Single Phase Vault				CY: 0.9 yds3	SCALE: 1:20		
	DRAWN BY:EP	DATE DRAWN: 04MAR25	PM:	RELEASED FOR PROD.:		APPROX. DELIVERY:		WEIGHT: 3620 lbs	SHEET: 1/1		